McEver and Lights Ferry Road Roundabout

Attachment #001 **CONSTRUCTION PLANS** FOR

LOCATED IN HALL COUNTY, GEORGIA 2nd. DISTRICT



NO PART OF THE PROJECT SITE IS LOCATED WITHIN 1 MILE OF AN IMPAIRED STREAM .

THERE ARE NO STATE WATERS REQUIRING A 50' OR 100' UNDISTURBED BUFFER ON THE SITE OR WITHIN 200 FEET OF THE SITE.

NO PART OF THE SITE IS LOCATED IN THE 100 YEAR FLOOD PLAIN PER HALL COUNTY FUTURE FLOOD ZONE



Know what's DOLOW. CALL before you dig.

Hall County Project Manager Franklin P. Miller. P.E. fmiller@hallcounty.org 770 470-691-4244

City of Flowery Branch Rich Atkinson rich@flowerybranch.org 770 967-6371

City of Gainesville Department of Water Resources Nick Swafford nswafford@gainesvillega.gov 770 538-2452

DRAWING INDEX

SHEET

- DESCRIPTION
- COVER SHEET C-1
- GENERAL NOTES C-2
- C-3 TYPICAL SECTIONS
- DEMOLITION PLAN C-4
- C-5 CONSTRUCTION/STAKING PLAN
- C-6 GRADING/DRAINAGE PLAN
- C-7 RIGHT OF WAY PLAN
- C-8 UTILITY PLAN
- SIGNING/STRIPING PLAN C-9
- C-10 PROFILES
- C-11 EROSION CONTROL PLAN
- C-12 LANDSCAPE PLAN
- C-13 DETAILS
- C-14 DETAILS

HALL COUNTY CONTACT: FRANK MILLER 770-531-6800

> 24 HR CONTACT: FRANK MILLER 770-531-6800



CONSTRUCTION GENERAL NOTES:

THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING THE ENTIRE CONSTRUCTION LIMITS DURING CONSTRUCTION. A PRECONSTRUCTION MEETING IS REQUIRED PRIOR TO COMMENCEMENT OF CONSTRUCTION.

- CONTRACTOR SHALL INSURE ACCESS IS MAINTAINED TO ALL ADJACENT PROPERTIES. 1
- 2. CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION.
- 3. CONTRACTOR SHALL STORE ALL EQUIPMENT AND MATERIAL IN A LOCATION CLEAR OF TRAFFIC AND APPROVED BY HALL COUNTY.
- 4. CONTRACTOR SHALL MAINTAIN TRAFFIC AT ALL TIMES. ANY DETOURS OR ROAD CLOSURES SHALL BE APPROVED BY HALL COUNTY TRAFFIC ENGINEER AND SHALL MEET THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD)
- 5. ALL ROADWAY SUBGRADE AND BASE SHALL BE COMPACTED TO 98% STANDARD PROCTOR. HALL COUNTY INSPECTOR MAY REQUIRE "ROLL TESTS" AS DEEMED NECESSARY USING A 20 TO 30 TON OR OTHER SIMILAR VEHICLE.
- WHEN SITE IS APPROVED BY HALL COUNTY ENGINEERING, THE SITE SHALL BE CLEAN AND 6. NEAT CONDITION. ALL DEBRIS, VEGETATION AND SPOILS SHALL BE REMOVED.

CONSTRUCTION SEQUENCE:

THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT EROSION IS MINIMIZED AND THAT COMPLIANCE WITH ALL APPLICABLE FEDERAL, STATE, AND LOCAL LAWS, REGULATIONS, AND ORDINANCES IS MAINTAINED THROUGHOUT EXECUTION OF THIS PROJECT.

- 1. OBTAIN A LAND DISTURBING PERMIT. SCHEDULE A PRE-CONSTRUCTION MEETING.
- 2. INSTALL GRAVEL CONSTRUCTION PAD, TEMPORARY DIVERSIONS, SILT FENCE, SEDIMENT TRAPS OR OTHER MEASURES AS SHOWN ON THE APPROVED PLAN. CLEAR ONLY AS NECESSARY TO INSTALL THESE DEVICES. SEED TEMPORARY DIVERSIONS, BERMS AND BASINS IMMEDIATELY AFTER CONSTRUCTION. SEE DETAIL ON SEEDING SCHEDULE. CONTRACTOR SHALL BEGIN WITH SEDIMENT FENCING AND ALL OTHER SEDIMENT CONTAINMENT DEVICES FOLLOWED BY ALL DIVERSION AND BY-PASS DITCHES/BERMS.
- BEGIN CLEARING/GRUBBING AND GENERAL EXCAVATION ON SITE. IT IS THE 3 RESPONSIBILITY OF THE CONTRACTOR TO PHASE/STAGE EROSION CONTROL TO ALLOW FOR CONSTRUCTION. NOTE: CONTRACTOR SHALL INSPECT AND REPAIR ALL EROSION DEVICES AT LEAST ONCE A WEEK AND AFTER EVERY RAINFALL. GRADING ACTIVITY SHALL BE PROHIBITED IN THE AREAS OF THE SEDIMENT CONTROL DEVICES/SEDIMENT TRAPS UNTIL THE AREAS UPSTREAM OF THESE DEVICES HAVE BEEN STABILIZED AND APPROVED.
- 4. BEGIN INSTALLING UPSTREAM STORM DRAINAGE SYSTEM. INSTALL APPROVED INLET PROTECTION. TERMINATE STORM DRAINAGE SYSTEM AT TEMPORARY SEDIMENT TRAP DEVICES UNTIL SUCH DEVICES HAVE BEEN APPROVED FOR REMOVAL. ADDITIONAL MEASURES MAY BE REQUIRED BY THE INSPECTOR DUE TO THE ROUTING OF THE STORM DRAINAGE SYSTEM AND ACTUAL FIELD CONDITIONS: NOTE: SEDIMENT BASINS SHALL BE FUNCTIONAL THROUGHOUT GRADING AND EXCAVATING.
- 5. STABILIZE SITE AS AREAS ARE BROUGHT UP TO FINISH GRADE WITH VEGETATION, PAVING, DITCH LININGS, ETC.. SEED AND MULCH DENUDED AREAS WITHIN FIFTEEN (15) DAYS OF COMPLETION OF ANY PHASE OF CONSTRUCTION: NOTE: THE CONTRACTOR SHALL ENSURE THAT THE EROSION CONTROL DEVICES REMAIN UNDISTURBED DURING CONSTRUCTION OF THE BUILDING PADS AND ASSOCIATED PARKING/DRIVE AREAS ADJACENT TO THESE DEVICES UNTIL THE CONTRIBUTING UPSTREAM AREAS HAVE BEEN STABILIZED AND APPROVED.
- 6. WHEN SITE IS APPROVED. REMOVE TEMPORARY DIVERSIONS. SILT FENCING. SEDIMENT BASINS, ETC... AND SEED OUT OR PAVE ANY RESULTING BARE AREAS. CONNECT UPSTREAM STORM DRAINAGE.

GRADING/EROSION CONTROL NOTES

- 1. ALL GRADING, BACKFILLING, EXCAVATION, ETC..., SHALL BE IN ACCORDANCE WITH THE RECOMMENDATIONS SET FORTH IN THE GEOTECHNICAL INVESTIGATION REPORTS. REFER TO THESE REPORTS FOR ADDITIONAL INFORMATION NOT TRANSFERRED TO THESE PLANS.
- 2. CONTRACTOR IS TO CONTACT UTILITIES PROTECTION CENTER AT 800-282-7411 FOR UNDERGROUND UTILITY LOCATION 3 DAYS PRIOR TO ANY DIGGING
- 3. THE EROSION CONTROL MEASURES ARE TO BE IN PLACE PRIOR TO ANY EARTHWORK.
- 4. ALL EROSION CONTROL MEASURES SHALL BE MAINTAINED UNTIL DISTURBED AREAS ARE STABILIZED.
- 5. ALL EROSION CONTROL FACILITIES SHALL BE INSPECTED AND REPAIRED AT A MINIMUM OF WEEKLY BASIS AND AFTER EVERY RAIN EVENT.
- 6. ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIALS AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT-LADEN RUNOFF TO ANY STORM DRAINAGE SYSTEM.
- 7. CONTRACTOR SHALL LOCATE AND VERIFY THE LOCATION OF ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION.
- 8. ALL CONSTRUCTION TRAFFIC SHALL ENTER AND EXIT THE SITE VIA THE CONSTRUCTION ENTRANCES.
- 9. THE APPROXIMATE AREA OF THE LIMITS OF CLEARING, GRADING, AND CONSTRUCTION IS 0.07 ACRES.
- 10 PURSUANT TO G.S. 113A-57(2), THE ANGLE FOR GRADED SLOPES AND FILLS SHALL BE NO GREATER THAN THE ANGLE THAT CAN BE RETAINED BY VEGETATIVE COVER OR OTHER ADEQUATE EROSION CONTROL DEVICES OR STRUCTURES. IN ANY EVENT, SLOPES LEFT EXPOSED WILL, WITHIN 21 CALENDAR DAYS OF COMPLETION OF ANY PHASE OF GRADING, BE PLANTED OR OTHERWISE PROVIDED WITH TEMPORARY OR PERMANENT GROUND COVER. DEVICES. OR STRUCTURES SUFFICIENT TO RESTRAIN EROSION. PURSUANT TO G.S. 113A-57(3), PROVISIONS FOR PERMANENT GROUND COVER SUFFICIENT TO RESTRAIN EROSION MUST BE ACCOMPLISHED FOR ALL DISTURBED AREAS WITHIN 15 WORKING DAYS OR 90 CALENDAR DAYS (WHICHEVER IS SHORTER) FOLLOWING COMPLETION OF CONSTRUCTION OR DEVELOPMENT.
- 11. ALL CUT AND FILL SLOPES AND CHANNEL SIDESLOPES WHICH ARE NOT TO BE PAVED, SHALL BE SEEDED UNTIL A GOOD STAND OF GRASS IS OBTAINED IN ACCORDANCE WITH: A. 100 LBS PER 1.000 SQUARE FOOT GROUND LIMESTONE OR EQUIVALENT. NO SOIL
 - TEST REQUIRED FOR INITIAL ESTABLISHMENT. B. 20 LBS OF 10-10-10 FERTILIZER OR EQUIVALENT PER 1,000 SQUARE FOOT. C. VARIETIES TO BE SEEDED:
 - 1. SPRING SEEDING MARCH 1 APRIL 30; SPRING OATS 2.5 LBS PER 1,000 SQUARE FOOT.
 - 2. SUMMER SEEDING MAY 1 AUGUST 1; WEEPING LOVE GRASS AT 2 OZ. PER SQUARE FOOT MIXED WITH 1 BUSHEL OF SAWDUST FOR UNIFORM SEEDING.
 - 3. ASPHALT MULCH 6 GALLONS PER 1,000 SQUARE FOOT. ALL SEEDING WILL BE MULCHED.

MAINTENANCE NOTES:

IN GENERAL, ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CHECKED AND MAINTAINED DAILY AND AFTER EACH RAINFALL GREATER THAN 0.5 INCHES. ANY SEDIMENT THAT HAS BEEN TRANSPORTED BEYOND THE PROJECT LIMITS SHALL BE REMOVED. THE FOLLOWING ITEMS WILL BE CHECKED IN PARTICULAR:

CONSTRUCTION ENTRANCE:

INSPECT CONSTRUCTION ROADS AND PARKING AREAS PERIODICALLY FOR CONDITION OF SURFACE. TOPDRESS WITH NEW GRAVEL AS NEEDED. CHECK ROAD DITCHES AND OTHER SEEDED AREAS FOR EROSION AND SEDIMENTATION AFTER RUNOFF-PRODUCING RAINS. MAINTAIN ALL VEGETATION IN A HEALTHY. VIGOROUS CONDITION. SEDIMENT PRODUCING AREAS SHOULD BE TREATED IMMEDIATELY.

SILT FENCE:

INSPECT SEDIMENT FENCES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY. SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR, DECOMPOSE, OR BECOME INEFFECTIVE, REPLACE IT IMMEDIATELY. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE FENCE. TAKE CARE TO AVOID UNDERMINING THE FENCE DURING CLEANOUT. REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS AND BRING THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

SILT FENCE GRAVEL OUTLET:

INSPECT SEDIMENT FENCE GRAVEL OUTLETS AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN. ANY RIP RAP DISPLACED MUST BE REPLACED IMMEDIATELY.

OUTLET STABILIZATION STRUCTURE:

INSPECT RIP RAP STRUCTURES WEEKLY AND AFTER SIGNIFICANT (0.5 INCH OR GREATER) RAINFALL EVENTS TO SEE IF ANY EROSION AROUND OR BELOW THE RIP RAP HAS TAKEN PLACE, OR IF STONES HAVE BEEN DISLODGED. IMMEDIATELY MAKE ALL NEEDED REPAIRS TO PREVENT FURTHER DAMAGE.

BLOCK AND GRAVEL INLET PROTECTION:

INSPECT THE BARRIER OF AFTER EACH RAIN AND MAKE REPAIRS AS NEEDED. REMOVE SEDIMENT AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR SUBSEQUENT RAINS. WHEN THE CONTRIBUTING DRAINAGE AREA HAS BEEN ADEQUATELY STABILIZED. REMOVE ALL MATERIALS AND ANY UNSTABLE SOIL. AND EITHER SALVAGE OR DISPOSE OF IT PROPERLY. BRING THE DISTURBED AREA TO PROPER GRADE. THEN SMOOTH AND COMPACT IT. APPROPRIATELY STABILIZE ALL BARE AREAS AROUND THE INLET.

SEDIMENT TRAP:

INSPECT TEMPORARY SEDIMENT TRAPS AT LEAST WEEKLY AND AFTER RAINFALL EVENTS 0.5 INCHESOR MORE. REMOVE SEDIMENT AND RESTORE THE TRAP TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE-HALF THE DESIGN DEPTH OF THE TRAP. PLACE THE SEDIMENT THAT IS REMOVED IN THE DESIGNATED DISPOAL AREA, AND REPLACE THE PART OF THE GRAVEL FACING THAT IS IMPAIRED BY SEDIMENT.

CHECK THE STRUCTURE FOR DAMAGE FROM EROSION OR PIPING. PERIODICALLY CHECK THE DEPTH OF THE SPILLWAY TO ENSURE IT IS A MINIMUM OF 1.5 FEET BELOW THE LOW POINT OF THE EMBANKMENT. IMMEDIATELY FILL ANY SETTLEMENT OF THE EMBANKMENT TO SLIGHTLY ABOVE DESIGN GRADE. ANY RIPRAP DISPLACED FROM THE SPILLWAY MUST BE REPLACED IMMEDIATELY.



Know what's DELOWA Call before you dig.

ENGINEERING DIVISION	HALL COUNTV DEPARTMENT		OF FUBLIC WUKNS	P.O. DRAWER 1435	GAINESVILLE, GA 30503	Phone: 770-531-6800 Fax: 770-531-3945
HAL	E We ha	C(O F			TV	-Y
CENERAL NOTES		MCEVER ROAD & LIGHTS FERRY ROAD		ROUNDABOUT IMPROVEMENT	HALL COUNTY GEORGIA	
DATE 12/1/22	6/15/23					
REVISION Issued for Construction	Added Sheet					
		ΗT				
- NO.	2.					
DRAWN CHECK DATE:	C N BY.	F.	M	11	ER	
ON CHECK DATE:			R G G TER		ER	





TYPICAL SECTION ROUNDABOUT

– R = 1 ft (0.3 m)

– R = 1 ft (0.3 m)

RAISED CONCRETE ISLAND

Offset 3 ft (1 m) down to 1 ft (0.3 m)

All concrete shall be 4000 PSI. All sub-base shall be compacted to 98% Standard Proctor. Mill asphalt at all ties, inlay for smooth transition.

ENGINEERING DIVISION	HALL COUNTY DEPARTMENT OF PUBLIC WORKS	P.O. DRAWER 1435 GAINESVILLE, GA 30503 Phone: 770-531-6800 Fax: 770-531-3945				
HAL	L CO E O R O Ve have it all i					
TYPICAL SECTIONS	TYPICAL SECTIONS McEVER ROAD & LIGHTS FERRY ROAD ROUNDABOUT IMPROVEMENTS HALL COUNTY, GEORGIA					
DATE 12/1/22	6/15/23					
REVISION Issued for Construction	Kevised Island					
CHECKEI DATE:	ову. 5/3/21	BN				
K PROFESSIONAL PROFESSIONAL CALIFIC INEER FT. F. CINEER FT. F						
(C- 3	3				











5" YELLOW

ATETD .

EROSION CONTROL NOTES

1.	OWNER	HALL COUNTY BOARD OF COMMISSIONERS 2875 BROWNS BRIDGE ROAD GAINESVILLE, GA. 30504 (770) 531-6800
2.	EMERGENCY 24-HOUR CONTACT	FRANKLIN P. MILLER, P.E. (770) 531-6800
3.	PROJECT DESCRIPTION	THE LAND DISTURBING ACTIVITY CONSIST OF EXPANDING AN EXISTING ROADWAY TO PROVIDE FOR A SINGLE LANE ROUNDABOUT AT HOG MOUNTAIN ROAD AND CASH ROAD. THE TOTAL AFFECTED AREA IS 7.48 ACRES. TOTAL NEW CLEARING AREA= 0.24 ACRES THE TOTAL AMOUNT OF EARTHWORK IS 2,800 CY WITH 2,800 CY IN FILL. THE PROJECT WILL BE AN ASPHALT OVERLAY AND THE CONSTRUCTION OF A ROUNDABOUT.
4.	EXISTING SITE CONDITIONS	THE TOPOGRAPHY IS FLAT WITH NO TREES OR GRASSY AREAS. THE CURRENT SITE IS AN EXISTING ROADWAY. THE AREA DRAINS FROM EAST TO WEST.
5.	ADJACENT AREAS	NORTH: McEVER ROAD SOUTH: McEVER ROAD EAST: LIGHTS FERRY ROAD WEST: LIGHTS FERRY ROAD
6.	CRITICAL AREAS	NO CUT OF FILL SLOPESSTEEPER THAN 2:1 ARE ALLOWED. CARE SHALL BE TAKEN TO PROTECT STREAMS AND EXISTING AREAS FROM SEDIMENT INFILTRATION. SPECIAL ATTNETION WILL BE GIVEN TO FILLS OVER 5' IN HEIGHT.
7.	EROSION CONTROL MEAS ADDITIONAL EROSION CC WHERE DETERMINED NEC ACTUAL SITE CONDITION	URES SHOWN ON THE DRAWINGS ARE MINIMUM REQUIREMENTS. INTROL MEASURES SHALL BE EMPLOYED BY THE CONTRACTOR CESSARY BY LOCAL AUTHORITIES OR THE ENGINEER BASED UPON S.
8.	EROSION CONTROL MEAS DRAWINGS IF DRAINAGE DRAINAGE PATTERNS SHO RESPONSIBILITY TO ACCO CREATED AT VARIOUS ST	URES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE OWN ON THE DRAWINGS. IT IS THE CONTRACTOR'S OMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS AGES DURING CONSTRUCTION.
9.	PROVISIONS TO PREVENT CONFORMANCE WITH THI SEDIMENTATION CONTRO	EROSION OF SOIL FROM SITE SHALL BE, AS A MINIMUM, IN E LATEST REVISION OF THE "MANUAL FOR EROSION AND DL IN GEORGIA."
10.	FAILURE TO INSTALL, OP RESULT IN ALL CONSTRU MEASURES ARE CORRECT	ERATE, OR MAINTAIN ALL EROSION CONTROL MEASURES WILL CTION BEING STOPPED ON THE JOB SITE UNTIL SUCH ʿED.
11.	IF FINES OR PENALTIES A BECAUSE OF A LACK OF E BE RESPONSIBLE FOR PAY FINES OR PENALTIES SHA	RE LEVIED AGAINST THE PROPERTY OR THE PROPERTY OWNER CROSION OR SEDIMENTATION CONTROL, THE CONTRACTOR SHALL MENT OF SUCH FINES OR PENALTIES, OR THE COST OF SUCH LL BE DEDUCTED FROM THE CONTRACT AMOUNT.
12.	ALL MATERIALS SPILLED, PUBLIC ROADWAYS OR IN	, DROPPED, WASHED, OR TRACKED FROM VEHICLE OR SITE ONTO TO STORM DRAINS SHALL BE REMOVED BY THE END OF THE DAY.
13.	PRIOR TO COMMENCING I DISTURBANCE SHALL BE RIBBONS, OR OTHER APPE AUTHORIZED LAND DISTU OF THE CONSTRUCTION A THE LIMITS INDICATED O	LAND DISTRUBANCE ACTIVITY, THE LIMITS OF LAND CLEARLY AND ACCURATELY DEMARCATED WITH STAKES, ROPRIATE MEANS. THE LOCATION AND EXTENT OF ALL JRBANCE ACTIVITY SHALL BE DEMARCATED FOR THE DURATION CTIVITY. NO DISTURBANCE ACTIVITY SHALL OCCUR OUTSIDE N THE DRAWINGS.
14.	CONSTRUCTION ON THE S CONTROL MEASURES SUF SEDIMENT CONTROL MEA GROUND WITHIN THE CON PERMANENT VEGETATION	TTE WILL BEGIN WITH INSTALLATION OF EROSION FICIENT TO CONTROL SEDIMENT DEPOSITS AND EROSIONS. ALL SURES WILL BE MAINTAINED UNTIL ALL UPSTREAM DISTRUBED NSTRUCTION AREA HAS BEEN COMPLETELY STABILIZED WITH NAND ALL ROADS/PARKING HAVE BEEN PAVED.
15.	CONTRACTOR SHALL INSI BEFORE AND AFTER EACH	PECT AND REPAIR EROSION CONTROL MEASURES DAILY AND I ANTICIPATED RAINFALL.
16.	THE CONTRACTOR SHALL CHECK DAMS WHICH BEC	REMOVE ACCUMULATED SILT FROM SEDIMENT BARRIERS AND OME SILTED ABOVE ONE-HALF OF THEIR ORIGINAL HEIGHT.
17.	ALL AREAS TO BE PAVED PRACTICAL. TEMPORARY PROVIDED IMMEDIATELY	SHALL BE STABILIZED WITH BASE MATERIAL AS SOON AS OR PERMANENT VEGETATIVE STABILIZATION SHALL BE AFTER REACHING FINAL GRADE FOR ALL AREAS NOT TO BE PAVED.
18.	PERMANENT VEGETATION HAS BEEN COMPLETED.	N SHALL BE PROVIDED NO LATER THAN 7 DAYS AFTER GRADING
19.	TEMPORARY MULCHING S PERMANENT STABILIZAT	SHALL BE PROVIDED TO DISTURBED AREAS NOT TO RECEIVE ION WITHIN 14 CALENDAR DAYS OF BEING DISTURBED.
20.	WHEN ANY CONSTRUCTION DEPOSIT ANY BUILDING OF DEBRIS, ECT. IN THE DRAI	ON BORDERS A DRAINAGE COURSE, THE CONTRACTOR SHALL NOT OR OTHER EXCAVATION SPOIL DIRT, CONSTRUCTION TRASH OR NAGE COURSE OR ASSOCIATED FLOOD PLAIN.
21.	GRADING EQUIPMENT MU CULVERTS, EXCEPT WHEN WILL BE PERFORMED IN A EROSION AND SEDIMENTA	UST CROSS FLOWING STREAMS BY THE MEANS OF BRIDGING OR N SUCH METHODS ARE NOT FEASIBLE; ALL STREAM CROSSINGS ACCORDANCE WITH THE LATEST REVISION OF THE "MANUAL FOR ATION CONTROL IN GEORGIA."
22.	DISCHARGE OF STORM-W CONTROLLED TO THE EXT DISCHARGE SHALL NOT E TURBIDITY LEVEL OF THE STORM-WATER RUN-OFF	ATER RUN-OFF FROM DISTURBED AREAS TO A STREAM SHALL BE TENT THAT TURBIDITY OF THE STREAM DOWNSTREAM FROM THE XCEED 25 NEPHELOMETRIC TURBIDITY UNITS HIGHER THAN THE E RECEIVING STREAM IMMEDIATELY UPSTREAM FROM THE DISCHARGE AT THE TIME OF SUCH DISCHARGE.
23.	DISPOSE OF WASTE SOILS SECURED BY THE CONTRA REGULATIONS.	AND CLEARED AND GRUBBED MATERIALS OFF-SITE AT A LOCATION ACTOR, AND IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL
24. 25	ALL FILL SLOPES WILL HA	AVE SILT FENCES AT THE TOE OF SLOPES.
23.	ALL EROSION AND SEDIM DEFICIENCIES WILL BE CO CONTROL MEASURES WIL BY THE ISSUING AUTHOR	ENT CONTROL MEASURES WILL BE INSPECTED DAILY, AND ANY DRRECTED BY THE END OF EACH DAY. ADDITIONAL EROSION IL BE INSTALLED IF DEEMED NECESSARY BY ON SITE INSPECTION ITY.
26.	SURFACE ROUGHENING (S AND VEGETATED WITHIN	Su): ALL CUT AND FILL SLOPES SHALL BE SURFACE ROUGHENED SEVEN DAYS AFTER GRADING IS COMPLETED.
27. 28.	THIS SITE DOES CONTAIN	STATE WATERS. WETLANDS.
29.	THE INSTALLATION OF ER PRIOR TO, OR CONCURREN	OSION CONTROL MEASURES AND PRACTICES SHALL TAKE PLACE
30.	THIS PROPERTY IS NOT LC	DCATED IN A FLOOD HAZARD AREA AS PER PANEL
31.	THIS PROPERTY IS NOT LC	ICATED IN A FLOOD HAZARD AREA AS PER PANEL
32.	STORM WATER MANAGEM	MENT
	THE EXISITNG PERMITTED MANAGEMNT FACILITIE S HAS BEEN PROVIDED ALO	O SITE " APARTMENT PROJECT" HAS PROPOSED STORM WATER PECIFICALLY PERTAINING TO DETENTION. A WATER QUALITY BASIN NH WITH A WATER QUALITY REPORT.

RIC MH.	ENGINEERING DIVISION HALL COUNTY DEPARTMENT OF PUBLIC WORKS P.O. DRAWER 1435 GAINESVILLE, GA 30503 Phone: 770-531-6800 Fax: 770-531-3945
ию.	HALL COUNTY G E O R G I A We have it all in Hall
ARD	DETAILS MCEVER ROAD LIGHTS FERRY ROA ROUNDABOUT IMPROVEMENT HALL COUNTY, GEORGIA
	CHECKED BY.
RD	DATE: