

no.	date	by	ckd	description
0	8/28/23	MLA	BSW	ISSUED FOR BID

- NOTES:
- EXISTING TOPOGRAPHY BASED ON SURVEY COMPLETED BY ROCHESTER & ASSOCIATES, INC. DATED OCTOBER 2019 AND SUPPLEMENTAL SURVEY OF CELL 3 AND 4 AREA COMPLETED BY MAXWELL-REDDICK AND ASSOCIATES DATED APRIL 2023.
  - HORIZONTAL DATUM BASED ON NAD 83 GEORGIA STATE PLANES, WEST ZONE. VERTICAL DATUM BASED ON NAVD 88.
  - DESIGN CONTOURS WITHIN CELL 3 REPRESENT TOP OF LEACHATE DRAINAGE LAYER. DESIGN CONTOURS OUTSIDE OF CELL 3 REPRESENT FINISHED GRADES.
  - CONTOUR INTERVAL IS TWO FEET.
  - ROAD GRADES SHOWN IN THE HIGHLIGHTED AREAS ARE INTENDED TO FACILITATE CONSTRUCTION ACCESS, BUT DO NOT REPRESENT FINAL FINISHED GRADES. PLAN FOR FINISHED GRADES IN THESE LOCATIONS WILL BE PROVIDED VIA FUTURE ADDENDA.
  - LIMIT MARKER POSTS SHALL BE PLACED EVERY 100-FEET ALONG THE WEST BOUNDARY OF CELL 3.
  - CONTRACTOR SHALL USE 45° LONG RADIUS SWEEP ELBOWS FOR PIPE CONSTRUCTION. 90° ELBOWS SHALL NOT BE USED ON PROJECT.



4004 SUMMIT BLVD NE, SUITE 1200  
ATLANTA, GA 30319  
770-587-4776  
Burns & McDonnell Engineering Co., Inc.  
COA: PEF00100 (EXP DATE: 6/30/2024)


date	detailed
AUGUST 28, 2023	M. AULT
designed	checked
M. AULT	B. WELDON



CANDLER ROAD LANDFILL  
PERMIT #: 069-15D(MSWL)  
HALL COUNTY, GEORGIA

**PHASE II CELL 3 CONSTRUCTION**  
**LEACHATE COLLECTION SYSTEM PLAN**

project	152292	contract	PO # 435114
drawing	<b>C006</b>	rev.	<b>0</b>
sheet	11	of	39 sheets
file	C006 Leachate Collection System Plan.dwg		



0 60 120  
SCALE IN FEET



Scale For Microfitting  
Millimeters

Inches