



Hall County Government  
FINANCIAL SERVICES  
PURCHASING DIVISION

# Task Order #2026-003

May 19, 2025

POST OFFICE DRAWER 1435  
GAINESVILLE, GA 30503

t: 770.535.8270 | f: 770.531.6711

FINANCIAL SERVICES DIRECTOR  
Taylor Samples, CPA

ASSISTANT FINANCE DIRECTOR  
Elizabeth White

PURCHASING MANAGER  
Andy Penick

## For the provision of Resurfacing 29.96 Miles of Hall County Roads

Demand Services for On-Call Paving & Full Depth Reclamation Contract  
#42-002

### PROJECT DESCRIPTION

Hall County, Georgia Board of Commissioners' Public Works Department is issuing this Task Order #2026-003 to Demand Services for On-Call Paving & Full Depth Reclamation contractors to resurface approximately 29.96 miles of various Hall County roads according to the Scope of Work and Georgia Department of Transportation (GDOT) standards.

### SCHEDULE OF EVENTS

**Release Date:** Monday, May 19, 2025

**Pre-bid Site Visit:** Bidders are welcome to visit each site at their leisure.

**Bidder Questions Due Date:** Friday, May 30, 2025. Send questions to [andrew.youngblood@hallcounty.org](mailto:andrew.youngblood@hallcounty.org).

**Response to Bidder Questions Due Date:** Monday, June 2, 2025

**Bid Due Date:** Thursday, June 5, 2025, by 2:00pm

Bidders must respond with their Task Order proposals via e-mail to [andrew.youngblood@hallcounty.org](mailto:andrew.youngblood@hallcounty.org) by 2:00pm EST, Thursday, June 2, 2025. The County's Project Manager is:

Blair Reynolds, Project Engineer  
Hall County Public Works Department  
Office: (770) 531-6800  
[breyolds@hallcounty.org](mailto:breyolds@hallcounty.org)

### SPECIFICATIONS and SCOPE OF WORK:

This project is for the resurfacing of approximately 29.96 miles of various County roads listed on *Attachment C – Road Schedule*. The awarded contractor will be required to install asphalt pavement as specified in the specifications, and any required striping.

A pre-bid meeting is not required; however, Contractors are welcome to visit each site individually at their leisure. The awarded Contractor will be required to attend a pre-construction meeting scheduled by the Hall County Project Engineer. The awarded Contractor is required to provide,

in hard copy and thumb drive format, a construction schedule produced in Microsoft Project at the time of the scheduled pre-construction meeting.

#### Schedule

The awarded Contractor will be responsible for preparing all roads listed on *Attachment C – Road Schedule*. The line item for patching shall include the Contractor removing the defective material, disposing of the waste, delivering the asphalt, and installing the new hot mix asphalt. This patching work may be accomplished by milling and inlaying with full depth asphalt or by other means as approved by the project engineer. The project engineer shall specify the locations and depth of the patching done by the awarded Contractor. The awarded Contractor may estimate a depth of 2" of asphalt patch for bidding purposes.

**The completion date for this project is June 30, 2026.** Equal time extension will be given if the anticipated awarding date of the contract is delayed. Required completion dates are the dates that all work is to be completed. Hall County expects the awarded Contractor to begin work within 10 business days of the issuance of a Notice to Proceed and to maintain adequate progress to ensure the contract is completed by completion date. The awarded Contractor must include any anticipated inclement weather days and Holiday days within the allowed contract time. See Attachment "A" for information on inclement weather days. Hall County may consider any unusual number of inclement weather days for time extension.

Contractor is to notify Blair Reynolds, Hall County Project Engineer, at 770-531-6800 to keep him advised of any weather delay days, delays associated to utility facility relocation delays, or other delays in contract time.

#### Traffic Control

The awarded Contractor shall provide traffic control to include all items necessary to maintain safe travel for the public. Traffic control shall include, but is not limited to, road closed signs, barricades, detour signs, flagging, work zone signs, low/soft shoulder signs, etc. All traffic control devices and work zones shall comply with the Manual on Uniform Traffic Control Devices (MUTCD), latest edition. All traffic control items shall be maintained by the Contractor at all times throughout the length of the project. The low/soft shoulder signs shall be maintained until vegetation is established on the shoulders.

#### Inspections

A Hall County Engineer or Engineering Inspector will be on-site during the entire resurfacing process for all those projects. Work hours will be Monday through Friday, 8am to 5pm. Please contact the Project Engineer to schedule resurfacing work at least 24 hours in advance.

#### General

All design, detailing, fabrication, construction, and construction vehicles shall conform to the State of Georgia Department of Transportation, Standard Specifications of Transportation Systems, 2001 edition, unless otherwise noted.

Contractor is required to properly dispose of all removed driveway concrete. No concrete shall be buried within the right-of-way.

Quantities are approximate only. Actual quantities for pay items will be derived by field measurements and weight measurements. Contractor is to field verify the widths of all roads. Resurfacing shall be over existing asphalt only.

The Contractor shall install all required striping as quickly as possible but no longer than 24 hours after the road is completed unless directed otherwise by the project engineer.

The Contractor is required to construct shoulders on this project.

The Contractor shall be responsible for the replacement of any and all Traffic Signal Loops located on this project.

The Contractor shall deliver **all millings** to the Hall County Landfill located at **1700 Oakbrook Drive, Gainesville, GA 30507**.

The Contractor shall utilize the Leveling Electronics on the Asphalt Spreader on any roads that are longer than 1 mile in length unless otherwise directed by the Hall County Inspector.

Crack Sealing Scope:

The following roads are the **only** roads to be considered for **crack sealing**:

Allen Road, Cook Drive, East Hall Road (Sec. 2), Evian Way, Fuller Road (Sec. 2), Hilldale Road, Joe Chandler Road (Sec. 2), Nancy Creek Road, Shoreline Drive, and Tapawingo Drive.

Spout Springs Road (Sec. 2) will be a 2" mill/inlay only. Patching will be minimal and will be determined by the Hall County Inspector.

Shoulder Construction

Any borrow/waste/disposal areas or borrow material needed as part of this bid item in order to complete shoulder construction is included in the overall bid item. Contractor is required to delineate borrow/waste/disposal areas to the Hall County Project Engineer for his approval. Erosion and Sedimentation Control measures are required on any borrow/waste/disposal areas as part of the overall bid price.

The Contractor is to build shoulders on all base and pavement projects as directed by the Project Engineer. Shoulder construction consists of building up the shoulder elevation to match the new pavement elevation and extending this new built-up material to the point where the shoulder begins to drop off into the ditch or fill slope. This build up is not expected to be greater than six (6) inches in depth. The minimum required shoulder width is two (2) feet. The shoulders are to drain away from the pavement whenever possible. In the case where the existing shoulder was previously too high, the Contractor will tie in from the new pavement elevation to an appropriate point to provide satisfactory drainage. Whenever possible, the Contractor is expected to extend the shoulder width so as to retain the same shoulder width that occurs due to the higher elevation of the pavement. The Contractor is required to smooth and compact the new shoulder material with clean material that is free from rocky material that could create voids or cause poor turf establishment. The Contractor is required to remove all grubbing debris from new shoulder material. The Contractor is required to utilize an unerodible soil type so as to minimize repair trips at the Contractor's expense. The Contractor is required to sweep new pavement as shoulder construction activities proceed.

The Contractor is to install temporary shoulders as needed to ensure that the elevation difference between the pavement edge and the shoulder is a maximum of two and one half (2 ½) inches or less. Permanent shoulders shall be constructed as soon as possible after the road is completed. Payment for temporary shoulders shall be included in the unit price for shoulder construction. There will be no separate payment for temporary shoulders.

Bidding Information

Hall County reserves the right to delete or add quantities to best serve the interests of the county.

Allied Paving Contractors, Inc.  
(Full Legal Corporate Name)

By: [Signature]

Title: Vice President

Print Name: Bryan Jones

Sworn to and subscribed before me this

12th Day of June, 2025.

Notary Public: [Signature]

Notary commission expires: \_\_\_\_\_



HALL COUNTY, GEORGIA

By: \_\_\_\_\_

David Gibbs, Chairman  
Hall County Board of Commissioners

Date: \_\_\_\_\_

Attestation: \_\_\_\_\_

Board of Commissioners Clerk

**APPROVED AS TO FORM**

[Signature]  
Nathaniel R. Anderson,  
Senior Assistant County Attorney