



Hall County Government

FINANCIAL SERVICES
PURCHASING DIVISION

Task Order #2027-007

July 30, 2026

POST OFFICE DRAWER 1435
GAINESVILLE, GA 30503

t: 770.535.8270 | f: 770.531.6711

FINANCIAL SERVICES DIRECTOR
Taylor Samples, CPA

ASSISTANT FINANCE DIRECTOR
Elizabeth White

PURCHASING MANAGER
Andrew Youngblood

For the provision of Construction Services for Stormwater Pipe Rehabilitation/Replacement at Elizabeth Ln. and Squirrel Nest Court

Demand Services for On-Call Public Works Contractors – Contract #44-004 & Paving and Full Depth Reclamation – Contract #47-004

PROJECT DESCRIPTION

Hall County, Georgia Board of Commissioners' Public Works Department is issuing this Task Order #2027-007 to On-Call Public Works Contractors and Paving and Full Depth Reclamation Contractors to replace two (2) existing 84" corrugated metal pipes (CMP), approximately 70 feet long, located at Elizabeth Lane and Squirrel Nest Court (34.154171, -83.887476) in accordance with the Scope of Work and Georgia Department of Transportation (GDOT) specifications.

SCHEDULE OF EVENTS

Release Date: Thursday, July 30, 2026

Mandatory On-Site Pre-bid Meeting: Thursday, August 6, 2026, at 9:00am Eastern Time.

Bidder Questions Due Date: Tuesday, August 11, 2026. Send questions to andrew.youngblood@hallcounty.org

Response to Bidder Questions Due Date: Thursday, August 13, 2026

Bid Due Date: Monday, August 17, 2026, by 12:00pm Eastern Time

Bidding Process: Bidders must respond with their Task Order proposals via e-mail to andrew.youngblood@hallcounty.org by Thursday, August 11, 2026.

Bid Response: Complete the information below and return it to the Issuing Officer via email, by the date and time specified above. Electronic signatures are acceptable.

Taxes: The County is exempt from State of Georgia Local Sales and Use Tax. The Bidder understands and acknowledges that it is responsible for any sales and use taxes it may incur. The Bidder will not charge or invoice the County any sales and use tax as a separate line item. The Contractor may request a copy of the County's Georgia Sales and Use Tax Exemption Certificate.

Performance and Payment Bonds: A bid bond equal to five percent (5%) of the bid amount is required. Additionally, all Bidders must include in their bid submissions a letter of bondability. The County will only accept surety companies licensed to do business in the State of Georgia. The awarded Bidder must produce a performance and a payment bond that are both equal to 100% of the face value of the awarded amount. Performance and payment bonds must be received by the County before a Notice to Proceed is issued.

Liquidated Damages: Liquidated damages are assessed for each calendar day that exceeds Final Completion from the receipt of a Notice to Proceed. In the event that the Contractor unreasonably delays completion of the project or abandons the project before completion, the Contractor shall pay the County liquidated damages in the total amount of per calendar day until final completion as outlined in the table below.

Schedule of Deductions for Each Day of Overrun in Contract Time		
Original Contract Time		Daily Charges
From More Than	To and Including	Calendar Day, Completion Date, or Available Day
\$0	\$500,000	\$84
\$500,000	\$1,000,000	\$151
\$1,000,000	\$2,000,000	\$247
\$2,000,000	\$5,000,000	\$391
\$5,000,000	\$10,000,000	\$713
\$10,000,000	\$20,000,000	\$1,191
\$20,000,000	\$40,000,000	\$1,869
\$40,000,000	-----	\$5,089

Task Order Completion Dates:

Seven (7) days from Notice to Proceed (NTP) to achieve Substantial Completion (open to traffic).

Fourteen (14) Days from Notice to Proceed (NTP) to achieve Final Completion (Punch List items complete).

Work Hours:

Work permitted Monday – Sunday at all hours. Nighttime work is permitted to meet completion deadlines.

SCOPE OF WORK:

Refer to the Plan Specifications attached below.

The Scope of Work includes the replacement of two (2) 84” corrugated metal pipes (CMP), approximately 70 feet long, with two (2) 84” reinforced concrete pipes (RCP) near the intersection of Elizabeth Lane and Squirrel Nest Court in Flowery Branch, Georgia.

Contractor will be required to:

- Remove and dispose of existing pipes
- Furnish and install new pipes
- Reconstruct existing roadway including paving, striping, and guardrail required to be removed/demolished for construction
- Provide appropriate traffic control

- Furnish and install adequate backfill and erosion control, including permanent stabilization.

TRAFFIC CONTROL:

Maintenance of Traffic Control plans will be prepared considering:

- Routes status as emergency/evacuation and/or school bus routes.
- Use of nighttime operations.
- Need for flaggers to maintain safe flow of traffic.
- Maintenance of adjacent property accesses.

UTILITY CONFLICT RESOLUTION:

The Contractor will conduct utility management, coordination, and utility observation services in accordance with the latest County utility relocation procedures and Georgia 811 Guidelines. The Contractor shall work with existing utilities in place and protect and avoid damage to the greatest extent practicable.

Existing facilities to remain in place during construction includes one (1) 8" waterline owned by the City of Gainesville. Contractor shall provide adequate cover for the existing

RIGHT-OF-WAY/EASEMENT:

The Contractor shall complete the scope of work in the existing County Right-of-Way (ROW) and drainage easements.

EROSION CONTROL:

Erosion control measures shall be installed, to the greatest practical extent, prior to construction and should be maintained throughout the construction in accordance with GWSCC requirements. Particular care shall be exercised along stream buffers, wetlands, open waters and other sensitive areas to ensure that these areas are not adversely affected.

Items to be Provided by Hall County:

- a) Culvert Replacement Plan Sheets and Specifications
- b) Construction Inspection Services including but not limited to
 - i. Review of installer qualifications and equipment
 - ii. Review of diversion plans for the erosion and sedimentation control during structure replacements
 - iii. Construction inspection of installed structures and quality control
 - iv. Approval of materials and methods during construction.
- c) Reconnaissance/Maintenance Data
- d) GIS Data
- e) ROW and Easement Mapping

General Notes:

All design, detailing, fabrication, construction, and construction vehicles shall conform to Hall County and the State of Georgia Department of Transportation, Standard Specifications of Transportation Systems, 2021 edition (or most recent edition), unless otherwise noted.

Strickland & Sons Pipeline, Inc.

(Full Legal Corporate Name)

By: [Signature]

Title: President

Print Name: Robert F Strickland

Sworn to and subscribed before me this

17 Day of August, 2026.

Notary Public: Jordan S. Wells

Notary commission expires: 3/13/2028


HALL COUNTY, GEORGIA

By: _____

David Gibbs, Chairman
Hall County Board of Commissioners

Date: _____

Attestation: _____
Board of Commissioners Clerk



Revised Exhibit C - Cost Proposal Worksheet/Schedule of Values

Pipe Replacement at Elizabeth Ln. @ Squirell Nest Court

Item Number	Description	Unit	Quantity	Unit Price	Total Price
150-1000	MOBILIZATION	LS	1	\$26,210.00	\$26,210.00
150-1000	TRAFFIC CONTROL	LS	1	\$27,250.00	\$27,250.00
	DETOUR SIGNAGE	EA	4	\$500.00	\$2,000.00
156-0100	LAYOUT & FINAL AS BUILT SURVEY	LS	1	\$6,000.00	\$6,000.00
	CLEARING AND GRUBBING	AC	1	\$8,000.00	\$8,000.00
163-0232	TEMPORARY GRASSING	AC	1	\$500.00	\$500.00
163-0240	MULCH	TN	0.33	\$750.00	\$247.50
163-0301	CONSTRUCT AND REMOVE CONSTRUCTION EXITS	EA	1	\$1,800.00	\$1,800.00
	REMOVAL AND DISPOSAL OF DEBRIS	TN	252	\$50.00	\$12,600.00
	BYPASS PUMPING	LS	1	\$22,500.00	\$22,500.00
	PROTECTION OF EXISTING UTILITIES	LS	1	\$4,500.00	\$4,500.00
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	506	\$5.00	\$2,530.00
	REGULAR EXCAVATION	CY	1,185	\$15.00	\$17,775.00
310-1101	GR AGGR BASE CRS, INCH INCL MATL	TN	185	\$42.00	\$7,770.00
402-4506	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TP II GP 2 ONLY, INC BITUM MATL & H LIME	TN	61	\$215.00	\$13,115.00
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	69	\$205.00	\$14,145.00
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	61	\$205.00	\$12,505.00
413-0750	TACK COAT	GL	560	\$4.00	\$2,240.00
500-3800	CLASS A CONCRETE, INCL REINF STEEL	CY	108	\$1,060.00	\$114,480.00
	REMOVAL AND DISPOSAL OF 84" STORM DRAIN PIPE	LF	160	\$45.00	\$7,200.00
550-1728	STORM DRAIN PIPE, 84 RCP	LF	160	\$1,383.00	\$221,280.00
	#57 BEDDING STONE	TN	370	\$45.00	\$16,650.00
603-2036	STN DUMPED RIP RAP, TP 1, 36 IN	SY	217	\$92.00	\$19,964.00
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE TP 3	EA	2	\$1,500.00	\$3,000.00
641-1200	GUARDRAIL, TP W	LF	300	\$66.00	\$19,800.00
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	300	\$5.00	\$1,500.00
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	700	\$5.00	\$3,500.00
700-6910	PERMANENT GRASSING	AC	0.33	\$1,800.00	\$594.00
700-7000	AGRICULTURAL LIME (perm grass)	TN	0.33	\$200.00	\$66.00
700-8000	FERTILIZER MIXED GRADE (grass)	TN	0.33	\$900.00	\$297.00
716-2000	EROSION CONTROL MATS, SLOPES	SY	1,626	\$1.25	\$2,032.50

Grand Total: \$ 592,051.00