



FIELD EVALUATION REPORT

2660 White Sulphur Road ♦ Gainesville, Georgia 30501 ♦ 770.536.5220 phone ♦ office@southerngeotech.com
14476 Duval Place West ♦ Suite 803 ♦ Jacksonville, Florida 32218 ♦ 904.374.2252

PROJECT NAME:	<u>4620 Settingdown Road</u>	DATE OF EVALUATION:	<u>July 31, 2026</u>
EVALUATED BY:	<u>Rodney Clark</u>	PROJECT NO:	<u>14770G</u>
WEATHER CONDITIONS:	<u>Mostly Sunny</u>	REPORT NO:	<u>141413</u>
CLIENT:	<u>Owner (Gaillard)</u>		

WE NOTE THE FOLLOWING:

A representative of our firm visited the above referenced site to evaluate the structure to allow the structure to be moved from its current location to a new home site.

The structure was constructed from conventional lumber consisting of 2x4 walls, 2x8 joists, 2x8 rafters and 2x6 blocking and framing bracing. The structure is currently supported on a crawl space foundation. The structure will be lifted, supported and transported on frame rails that will be capable to carry the structural loads of the structure.

As observed, the structure adequate for stability and is satisfactory for transportation to a new building site.



This report has been prepared for the exclusive use of our client and their designees for specific application to this project. Furthermore, we note that the results presented relate only to the items evaluated and/or tested, and variations can be present outside areas that were tested and/or evaluated. As such, no other warranty is expressed or implied. Last, this report shall not be reproduced, except in full, without the written approval of SGC, LLC.

Rodney Clark

Note that by electronic signature above, the SGC personnel confirms that the findings of this report are free from any commercial, financial, or other pressures including trade organizations rules that might adversely affect the independence, judgment, and/or integrity of the results provided.